

## DEPARTMENT OF TRANSPORTATION FEDERAL AVIATION ADMINISTRATION SPECIFICATION

## ASR TRANSPORTATION, ONSITE INSTALLATION, TESTING AND ACCEPTANCE

This amendment forms a part of FAA-E-2508 dated December 7, 1971.

Page 1, paragraph 2.1.1: Remove FAA-D-638, Instruction Books, Electronic Equipment.

Page 4, paragraph 3.5.1.2: Replace the first two sentences with the following: "Government furnished and installed power cable will be brought out in a conduit stub with 20 feet of slack cable under the Module "A" power panel. Conduit shall be provided and installed between Module "A" power panel and the stub beneath Module "A" power panel by the contractor. The incoming power cable shall be terminated by the contractor in the power panel."

Page 4, paragraph 3.5.1.3: Replace the last sentence with the following: "The tower heights for each site will be provided by the Government 90 days prior to each system delivery onsite."

Page 4, paragraph 3.5.1.6: Replace the second sentence with the following: "The contractor shall provide conduit between the underground entrance conduit stubs located under the radar cable junction box (RCJB) and the RCJB. The video and control cables, provided and installed by others, coming out of the conduit stubs will have 20 feet of slack. The contractor shall provide all required connectors."

Page 7, paragraph 3.12.7.3.2: Add the following: "In case of conflict between The National Electric Code and FAA-C-1217, FAA-C-1217 shall be followed."

Page 7, paragraph 3.12.7.3.3: Remove the following part of the first sentence: "including the standby power plant where installed."

\* \* \* \* \*